



Project:	Apex Cemetery Remediation	RFT No.:	2021-RFT-013
Addendum No.:	2	No. of Pages:	2
Doc. No.	P7201-791690383-98(1.0)	Date:	June 24, 2021

The following change(s) in the Tender Documents are effective immediately.
 This Addendum forms part of the Contract Documents.

ITEM	DESCRIPTION
2.1	<p>Bidder Question</p> <p>Question: Section 31 23 33 item 2.1.2.3 table for type 1 fill – Normally the type 1 fill can be composed of 5% of 20mm, will it be acceptable for this project?</p> <p>Answer: No, the acceptable fill for this project is shown within the table found in Section 31 23 33 item 2.1.1.3.</p>
2.2	<p>Bidder Question</p> <p>Question: Section 31 23 33 item 3.6.7 – Dispose of surplus and unsuitable excavated material in approved location, can we know where it will be?</p> <p>Answer: It is the responsibility of the Contractor to locate a suitable location to dispose of surplus and unsuitable material from the site, in-line with any applicable regulations.</p>
2.3	<p>Bidder Question</p> <p>Question: Appendix B Cost Submission Form item 11 – Will it be possible to use a very small excavator, (i.e. 5 tn) and small compactor?</p> <p>Answer: The Contractor may use machinery on the walk/access ways within the hand placed limits but not overtop of any of the existing burials. The City notes that it is crucial that no heavy equipment or machinery of any kind may travel over existing burials under any circumstance.</p>
2.4	<p>Bidder Question</p> <p>Question: Appendix B Cost Submission Form – Please describe what is intended by hand placed.</p>

Answer: Hand placed is to place material within the hand placed limits, limiting mechanical equipment to not travel over any existing burials. The intent is to use tools such as hand shovels and wheelbarrows to place material if it cannot be reached with an excavator or other equipment that is located outside of the 'hand place border'.

2.5 Bidder Question

Question: Appendix B Cost Submission Form item 13 – Some culverts are already broken; do you want to reuse them?

Answer: The City has recently inspected all the culverts and has found the existing culverts to be in good condition. Culverts are to be reused. Prior to removal, if culverts are found to be damaged, a City Representative is to be contacted to confirm damage prior to removal.

2.6 Bidder Question

Question: Is the contractor allowed to place material with the excavator bucket from outside the hand place border shown on dwg G09? In other words, never track on any grounds with mechanical equipment within the hand place border.

Answer: Mechanical equipment can be used but no mechanical equipment is permitted to travel over existing burials.

2.7 Public Opening

A virtual public opening will be held on July 2, 2021, at 1 PM EST. The phone-in details are:

Conference Call #: 1-855-703-8985
Conference Meeting ID: 336 649 2470

Colliers Project Leaders Inc.

Date: June 24, 2021

Distribution: All Bidders
File