

<u>Item</u>	<u>Description</u>	<u>Payment Clause</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Price</u>	<u>Amount</u>
1	Mobilization & demobilization including permits, property owner engagement & site setup	1.5.3	L.S.	1		\$ -
2	Traffic control, project signage and safety setup	1.5.4	L.S.	1		\$ -
3	Utility pole support including coordination with QEC for excavation wo	1.5.5	L.S.	1		\$ -
4	Survey of Existing Asphalt Roadway	1.5.6	L.S.	1		\$ -
5	Project removals/decommissioning including removal/decommissioning of existing utilidor mains, service lines, water bleeds, etc.on the ATCO loop	1.5.7	L.S.	1		\$ -
6	Reinstate existing landscaping features (boulders, bollards,etc.)	1.5.8	L.S.	1		\$ -
SERVICE CONNECTIONS						
8	Supply and install new water and sewer service laterals to existing buildings including water carrier pipe, and sanitary sewer lateral	1.5.10				
a)	Lot 184 - Type II - 100mm dia. water carrier pipe c.w. 25mm supply and 25mm return and 100mm sanitary sewer lateral		each	1		\$ -
b)	Lot 223 - Type II - 100mm dia. water carrier pipe c.w. 25mm supply and 25mm return and 100mm sanitary sewer lateral		each	1		\$ -
c)	Lot 247 - Type II - 100mm dia. water carrier pipe c.w. 25mm supply and 25mm return and 100mm sanitary sewer lateral		each	1		\$ -
9	Lot 243 - Supply and install new 100mm sewer service laterals from main to existing building	1.5.11	each	1		\$ -
10	Internal plumbing modifications within each private building	1.5.9 & 1.5.10	each	3		\$ -
ROAD WORKS						
11	Driveway reinstatement - supply and install all necessary granular reinstatement as required (100mm Granular A, 300mm Granular B)	1.5.12	L.S.	1		\$ -
PROVISIONAL ITEMS						
12	Sub excavation of unsuitable material including backfilling with Granular 'B'	1.5.13	m ³	40		\$ -
13	Supply, deliver, place, and compact Granular A	1.5.14	m ³	40		\$ -
14	Supply, deliver, place and compact Granular B	1.5.15	m ³	40		\$ -
15	Rock Excavation and Disposal Off-Site	1.5.16	m ³	10		\$ -
16	Off-site disposal of soil that is deemed contaminated	1.5.17	m ³	30		\$ -
17	Asphalt Road Reinstatement - 74mm Hot Mix Asphalt	1.5.18	m ²	120		\$ -
18	Cash Allowance-Road Reinstatement with Rigid Concrete Pavement	1.5.19	L.S.	1	\$ 120,000.00	\$ 120,000.00
SUBTOTAL						\$ -
GST 5%						\$ -
TOTAL						\$ -

END OF SECTION